

Energy Efficient Ventilated Façades for Optimal Adaptability and Heat Exchange enabling low energy architectural concepts for the refurbishment of existing buildings.



E2VENT WORKSHOP

DEMO IN SPAIN AND POLAND

Diego Romera
ACCIONA

30/05/2018

The project leading to this application has received funding from the European Union's Horizon 2020 research and innovation programme under grant agreement No 637261 .




Pilots



- Main objective:
 - Validation of the E2VENT deep renovation strategy
 - Assessment of
 - Robustness
 - Effectiveness
 - Viability
- Implementation and execution in two buildings
 - Different climate
 - Different typology of construction and use.
- Burgos:
 - University
 - Climate: Continental Moderate
- Gdansk
 - Residential
 - Climate: Marine West Coast
- Energy Goals
 - Reduction of 40% of primary energy consumption
 - Reduction of 40% of CO2 emissions
 - Reduce thermal and electrical peak loads



Project Management



- Technical assessment of the building:
 - HVAC systems
 - Constructive and architectural features
- Definitions of Energy Conservation Measures


- IPMVP protocol (What, why, how and where to measure)
- Definition of the monitoring plan

- Definition of technical requirements
- Engineering and architectural design

- Preparation of the site
- Manufacturing and transport of the materials and components
- Preassembling of the Prototypes
- Installation works

- Commissioning of the system:
 - * Communication between control and energy systems.
 - * Optimize performance.
 - * Airflow and acoustic test, etc.

- Assessment of:
 - * Improvement of Inner Comfort conditions
 - * Energy Savings
 - * Energy system operation and performance



Pilot site in Burgos






- University building in Burgos
- One-level block, with pitched roof, masonry walls of 65cm thickness , not-insulated
- Centralized heating system. No mechanical ventilation
- Related Pathologies:
 - Comfort:
 - Low Indoor Environmental Quality
 - Energy-Related Pathologies:
 - Poor Building Envelope
 - Low Performance of heating system



Pilot site in Burgos



- Two rooms of study: Lecture Room, PC Room
- Monitoring System
 - Energy Consumption
 - Internal comfort conditions
 - External weather conditions





Pilot site in Burgos




■ Proposed Renovation


- Envelope Upgrade
 - Ventilated façade
 - Ceiling insulation
 - Windows replacement
- HVAC upgrade (just PC Room)
 - Ventilation System with heat recovery (SMHRU)
 - Cooling System (LHTES)
 - Control System (BEMS)




Front elevation (South)
Scale 1:100




Side elevation (West)
Scale 1:100




Back elevation (North)
Scale 1:100




Detail 01
Scale 1:4



Detail 02
Scale 1:4



Detail 03
Scale 1:4



Detail 04
Scale 1:4

Pilot site in Burgos



- Manufacturing
- Pre-assembling in factory
- Transport to the site



Pilot site in Burgos



■ Installation


- Envelope: Ventilated façade modules, windows, insulation.
- Prototypes (LHTES, SMHRU)

■ Commissioning

- Dampers and fans
- Airtightness
- Air flow
- Acoustic



Pilot site in Burgos



Pilot site in Gdańsk






- Multi-family residential building in Nowy Port, Gdańsk
- External walls from full brick with thickness 38 cm, not-insulated
- 10 flats
- Individual heating system. No mechanical ventilation
- Related Pathologies:
 - Comfort:
 - Low Indoor Environmental Quality
 - Energy-Related Pathologies:
 - Poor Building Envelope
 - Low Performance of heating system



Pilot site in Gdańsk



- Two dwellings of study: ground floor, first floor
- Monitoring System
 - Energy Consumption
 - Internal comfort conditions
 - External weather conditions







Pilot site in Gdańsk



■ Proposed Renovation

- Envelope Upgrade
 - Ventilated façade (South orientation)
 - ETICS (West orientation)
- HVAC upgrade
 - Ventilation System with heat recovery (SMHRU)
 - Control System (BEMS)



Pilot site in Gdańsk



- Manufacturing
- Pre-assembling in factory
- Transport to the site
- Installation



Pilot site in Gdańsk



■ Commissioning

- fans
- Airtightness
- Air flow
- Acoustic



BEMs interface



Initial Schema Graphics Comfort

Sensors in flat

FLAT7_CO2: 431 ppm
FLAT7_HUM: 39.600 %
FLAT7_TEMP: 20.80 °C
FLAT7_CHIM_TEMP: 21.40 °C
FLAT2_CO2: 1444 ppm
FLAT2_HUM: %
FLAT2_TEMP: 20.20 °C

STORE DATA
Watch Data

Ventilation unit

CAVITY_TEMP: 9.8 °C
CAVITY_HUM: 65.200 %
T_AIR_REN_7: 7.70713 °C
DIFF_PRESS_1_7: 2.342935 Pa
DIFF_PRESS_2_7: 2.26566 Pa
T_AIR_EXP_7: 8.391518 °C
T_AIR_REN_2: 9.635284 °C
DIFF_PRESS_1_2: 130.7561 Pa
DIFF_PRESS_2_2: 141.0959 Pa
T_AIR_EXP_2: 11.35562 °C

Piloting rules

CURRENT_ZONE: Home_2

C_SPEED_V1_7_MAN (rpm): 2000 [update]
REF_V1_7: 0 rpm
SPEED_V1_7: 28.63841 rpm
SMHRU_ON_7: AUTO

C_SPEED_V2_7_MAN (rpm): 3000 [update]
REF_V2_7: 0 rpm
SPEED_V2_7: 28.66952 rpm
REF_CO2_7 (ppm): [update]


C_SPEED_V1_2_MAN (rpm): 0 [update]
REF_V1_2: 6850 rpm
SPEED_V1_2: 1598.979 rpm
SMHRU_ON_2: AUTO

C_SPEED_V2_2_MAN (rpm): 0 [update]
REF_V2_2: 6850 rpm
SPEED_V2_2: 1754.575 rpm
REF_CO2_2 (ppm): 650 [update]

Data analysis



- Pre-Monitoring data



- Post-Monitoring data: (Assessment in Progress)

- Energy Savings
- Comfort conditions improvement
- Performance of Energy devices (LHTES, SMHRU)



Thank you for your attention.

Diego Romera Pascual

Project Manager. Energy Engineer.

diego.romera.pascual.ext@acciona.com

